


57	Clamp for feeder connection	Kruch	FKL-01.7.50	5
56	Clamp for feeder connection	Kruch	FKL-01.2.50	4
55	Sormat cable clamps KP34			3
54	Sormat cable clamps KL34		9640013082	3
52	Washer M10	DIN 125, HDG		1
48	Cable Lug	Oxlip	R4-433	1
47	Hex screw M10x40	DIN 933-8.8, HDG		2
46	Cable lug	XMAR 1050-10		1
45	Cable terminator fastener part		10307	2
37	Cu-spring washer	DIN 127 CuSn8		1
31	Hex screw M12x50	DIN 933-8.8, HDG		1
30	Cu-Hex screw M12x50	DIN 933		1
29	Cu-Hex Nut	DIN 934, Cu		1
26	Washer M12	SFS 3737		2
25	Washer M10	SFS 3738, HDG		4
24	Cable lug Ostrich		499999043-02	2
23	Hex screw M16x50	DIN 933-8.8, HDG		1
20	Suspension clamp		SR-R-1368	1
19	Sormat cable clamps KP60			6
18	Sormat cable clamps KL60			6
17	I-post U14T92			1
16	Washer M12	DIN 125, HDG		1
15	Washer M16	DIN 125, HDG		3
14	Supp. insulator/over volt. protection device fastener beam		10552	1
12	Over voltage protection device fastener		10554	1
11	Post insulator	Pfisterer	805 023 003	2
10	Over voltage protection device 25kV	Tridelta SBK-I 42/10.1		2
9	Hex screw M16x180	DIN 931-8.8, HDG		4
8	Cable rack cover panel			4
8	Threaded rod M10x500	DIN 976-8.8, HDG	HDG	6
6	Cable rack vertical bracket	VK2, HDG	1320137	4
5	Wall fastener	VK2, HDG		12
4	Cable lug for wires 95 CuF and 120 Cu	R4-367		2
3	Cable rack KS80-200			2
2	Cable terminator fastener 52kV OHVT-5212 (XVKU 6196)			2
1	Cable terminator fastener	K36/52		2
NO	PART	DESCRIPTION	DOCUMENT NUMBER	QTY

Projekteerija Juuso Lampikoski	Joonis TSS4 Oru veoalajaama ühendamine raudtee kontaktvõrguga	Objekt Tapa-Narva raudtee elektrifitseerimine ja kontaktvõrgusüsteemi käitamine
Inspektor Janne Järvinen		Aadress Ida-Virumaa, Jõhvi vald, Linna küla, Kohtla metskond 166 km+m
Vastutav spetsialist Timo Hartikainen		
 GRK sial Oy Jätkökatu 2, 01620 Vantaa Finland e-post: firstname.lastname@grk.fi Business ID: 2810844-3	Teillija AS EESTI RAUDTEE	Staadium Eelprojekt
	Kuupäev 27.08.2025	Projekti tunnus 140004TSS4
		Mootkava 1:50
		Leht 1/1