

Pos Nr	märgistus	KKS	Nimetus ja tehniline iseloomustus	Tüüp	Ühik	Kogus	Märkus
Lahterid 6.3kV, 10.5kV							
1	70		Retrofit	1250A	kompl	1	
2	BBA009			1250A	kompl	1	
Trafod							
3	TV1		Trafo	BSA.24.211, 6.3/10.5 kV YNd11	kompl	1	BETA
Trafo ühendamine							
4			Siin 10 kV	AI 80x8	m	3	Arruti Subestaciones
5			Isolaator	NTWA 12 A 16	tk	6	ABB
6			Vertikaalne siini kinniti	PPV-80M 12	tk	6	Arruti Subestaciones
7			Otsmuhv 6 kV	POLT-12E/1XI-L16	tk	6	Tyco Electronics Raychem
8			Otsmuhv 10 kV	POLT-12E/1XI-L16	tk	6	Tyco Electronics Raychem
9			Kaabliking	BLMT-150/400 mk2-17	tk	6	ENERGY
10			Juhe	AAC 325, d=23.4mm	m	6	Arruti Subestaciones
11			Juhtmete kinniti	MRDP 2555	tk	3	Arruti Subestaciones
JS 10.5kV							
12							
Kaablid							
13	W01, W03a	<i>vt.kaabližurnaal</i>	Keskpingekaabel	AXLJ-TTCL TSLF 12/20(24)kV 1x400/35	m	3300	Draka
14	W03b	<i>vt.kaabližurnaal</i>	Keskpingekaabel	AXLJ-TTCL TSLF Triplex 12/20(24)kV 3x1x400/35	m	1300	Draka
15	W02	<i>vt.kaabližurnaal</i>	Keskpingekaabel	AXLJ-RMF 12/20kV 3x300/35	m	2850	Draka
16	W04	<i>vt.kaabližurnaal</i>	Keskpingekaabel	AXLJ-RMF 12/20kV 3x240/35	m	1050	Draka
17			Jätkumuhv	POLJ-24/1x150-300-CEE01	tk	12	Raychem

18			Otsamuhv	HIT1.1205L	tk	24	Ensto
19			Otsamuhv	HIT1.1204L	tk	12	Ensto
20			Otsamuhv	HIT1.1203L	tk	12	Ensto
21		<i>vt.kaabližurnaal</i>	Optikakaabel	FYO2RMU 2x12xSLM	m	1100	
22	W101, W103	<i>vt.kaabližurnaal</i>	Kontrollkaabel	NOMAK 24x2x0.5+0.5	m	1625	Draka
23	W102	<i>vt.kaabližurnaal</i>	Kontrollkaabel	NOMAK 4x2x0.5+0.5	m	125	Draka
Kaabliteed/ кабельные пути							
24			Kaabliredel	KS80-300 L=6000 HDG C4	m	360	MEKA
25			Kaabliredel	KS80-600 L=6000 HDG C4	m	331	MEKA
26			Kaabliredeli kaas (välispaigaldamiseks)	SK L=3000 HDG C4	m	186	MEKA
27			Kaabliredeli jätkukinniti	SSR HDG	tk	220	MEKA
28			Kaabliredeli kinniti	NL HDG	tk	26	MEKA
29			Kaabliredelinurk	KSV-300 R=600 HDG	tk	6	MEKA
30			Kaabliredelinurk	KSV-600 R=600 HDG	tk	4	MEKA
31			Profiil kinnituseks	AS L=6030 HDG	tk	7	MEKA
32			Kaabliredelikandur	AS 30 31 FT	tk	110	OBO Bettermann
33			Kaabliredelikandur	AS 30 61 FT	tk	69	OBO Bettermann
34			Kaabliredelikandur (välispaigaldamiseks)	VK-300 2KN HDG	tk	59	MEKA
35			Kaabliredelikandur (välispaigaldamiseks)	VK-600 2KN HDG	tk	59	MEKA
36			Profiil kinnituseks	IS 8 200 FT	tk	30	OBO Bettermann
37			Profiil kinnituseks	IS 8 300 FT	tk	20	OBO Bettermann
38			Kinnitid	AHIS 8 FT	kompl	120	OBO Bettermann
39			Travers	KI 8 NOK FT	tk	50	OBO Bettermann
40			Kaase kinniti (Konsool. Välispaigaldamiseks)	Konsool MFT-FOX VI 180 S 6.5	tk	372	Hilti
41			Kaabli klamber	KOZ UNI 3x 30-49	tk	1533	KOZ Products B.V.
42			Kaabli klamber	TRI 67-82	tk	500	KOZ Products B.V.
43			Liiv	67 tonn	m3	544	
44			Hoiatuslint		m	4680	
45			Kaitsetoru	Akl d=160	m	1240	

Maandus ja potentsiaaliühtlustus							
46			Juhe isoleeritud/ изолированный провод	120mm ²	m	50	REKA
47			Juhe isoleeritud/ изолированный провод	16mm ²	m	50	REKA
48			Juhe isoleeritud/ изолированный провод	6mm ²	m	100	REKA
49			Polt vedruseibiga ja mutriga, kuumtsingitud	M10/40	kompl	*	
50			Kuumrsingitud teras / полоса оцинкованая	40x4mm	m	*	
51			Kaabliking	120mm ²	tk	12	
52			Kaabliking	16mm ²	tk	*	
53			Kaabliking	6mm ²	tk	*	
54			Potentsiaaliühtlustuslatt	1802/10 CU 10XM10	tk	2	OBO Bettermann

* töövõtja kontrollib kogus paigaldustööde teostamise ajal