

Lisa 2. Uuringupunktide kataloog (2021., 2022. a ja 2017. a)

2021 ja 2022. a puuraugud

PA nr	Koordinaadid			PA süg., m	Katendi paksus, m	Kasuliku kihi jääkpaksus, m	sh savi vahekiht, m	Lamami, sügavus, m	Lamami abs kõrgus, m	Veetase, m		
	X	Y	Z							süg. maap, m	abs	mõõtmise aeg
Pa-1	6577139,82	703232,96	57,90	30,4	0,10	29,20	0,6	30,4+	28,60	17,5	40,40	11.01.2022
Pa-2	6577312,10	703174,49	55,61	32,6	0,10	26,91	2,4	32,60	28,60	15,0	40,61	19.01.2022
Pa-3	6577474,22	703053,25	61,97	30,4	0,10	30,25	-	30,35+	31,62	19,5	42,47	13.01.2022
Pa-4	6577498,56	702892,34	57,30	25,6	0,10	24,90	-	25,00	32,30	13,0	44,30	18.01.2022
Pa-5hg	6577558,40	702717,50	51,36	17,7	0,10	17,40	-	17,50	33,86	7,4	44,01	17.01.2022
Pa-6	6577396,23	702697,11	53,26	20,0	0,10	19,70	-	19,80	33,46	11,5	41,76	14.01.2022
Pa-7	6577465,34	703118,42	64,05	32,5	0,10	32,40	1,9	32,50+	31,55	20,0	44,05	20.01.2022
Pa-8	6577203,88	702673,24	49,57	13,7	0,40	12,15	-	12,55	37,02	4,5	45,07	09.06.2021
Pa-9	6577128,68	702627,76	51,31	16,9	3,00	13,00	-	16,00	35,31	5,6	45,71	09.06.2021
Pa-9a	6576961,34	702630,47	50,05	16,2	5,30	10,40	-	15,70	34,35	3,5	46,55	09.06.2021
Pa-10	6577033,28	702760,91	49,61	15,7	0,20	14,70	-	14,90	34,71	5,0	44,61	27.05.2021
Pa-11	6577080,08	702898,20	46,47	14,2	5,45	7,15	-	12,60	33,87	2,4	44,07	18.05.2021
Pa-12	6576771,69	702668,94	49,19	16,5	3,70	12,50	-	16,20	32,99	3,5	45,69	09.06.2021
Pa-13	6576848,81	702784,40	49,97	16,1	0,80	14,95	-	15,75	34,22	4,6	45,37	27.05.2021
Pa-14hg	6576640,35	702694,22	47,92	14,7	4,95	9,10	-	14,05	33,87	2,6	45,32	06.07.2021
Pa-15hg	6576675,36	702841,97	49,24	13,3	2,45	10,75	-	13,20	36,04	5,4	43,84	06.07.2021
Pa-16	6576869,13	702970,22	44,81	11,8	1,40	9,90	-	11,30	33,51	1,6	43,21	18.05.2021
Pa-18	6576501,13	702835,46	49,70	17,7	1,20	15,80	0,5	17,00	32,70	5,4	44,35	28.05.2021
Pa-19	6576579,26	703000,84	45,12	13,7	0,80	12,25	-	13,05	32,07	1,5	43,62	19.05.2021
Pa-21	6576301,95	702852,43	50,04	17,0	5,75	9,95	-	15,70	34,34	4,7	45,39	28.05.2021
Pa-21a	6576313,43	702976,55	43,96	10,5	2,95	7,25	-	10,20	33,76	0,7	43,31	19.05.2021
Pa-22	6576115,98	702781,55	50,43	15,7	5,70	9,70	-	15,40	35,03	4,5	45,93	20.05.2021
Pa-23	6576095,06	702950,79	45,78	13,8	1,40	9,10	-	10,50	35,28	2,6	43,18	19.05.2021
Pa-24a	6575874,08	702848,22	49,83	17,7	0,00	17,40	-	17,40	32,43	5,5	44,33	10.06.2021
Pa-24hg	6576004,09	702759,56	47,99	13,7	2,00	10,65	-	12,65	35,34	5,0	42,99	15.07.2021
Pa-25	6575904,68	702958,56	44,92	9,9	1,50	7,65	-	9,15	35,77	1,9	43,07	20.05.2021
Pa-26	6575719,58	702770,94	54,15	19,7	0,00	19,10	-	19,10	35,05	8,8	45,35	16.06.2021
Pa-27	6575720,59	702881,64	45,29	13,8	1,50	11,85	-	13,35	31,94	2,1	43,19	20.05.2021
Pa-29	6575530,10	702874,31	51,01	19,8	0,00	19,00	-	19,00	32,01	5,5	45,51	10.06.2021

2021. a nõlvapuhastused

NP nr	Koordinaadid			NP süg maa- pinnast, m	Katend kokku	Looduslik lasum, abs, m	Kasulik kiht kokku, m	uuritud abs	lamami abs*	Veetase, m		
	X	Y	Z							süg maap, m	abs	mõõtmise aeg
NP-1	6577304,45	702781,32	57,81	17,65	0,4	57,41	17,25+	40,16	33,54	14,58	43,23	29.07.2021
NP-2	6576671,33	702997,69	46,00	7,5	0,4	45,60	7,1+	38,50	31,76	2,77	43,23	29.07.2021
NP-3	6576452,70	703005,53	45,30	7,7	1,0	44,30	6,7+	37,60	30,65	2,07	43,23	29.07.2021
NP-4	6576221,97	702942,56	44,74	7,00	0,9	43,84	6.10+	37,74	32,81	1,51	43,23	29.07.2021

*lamami väärtused saadud mudelist

2017. a uuringupunktid (EGF 8890)

PA nr	Koordinaadid			PA süg., m	Katendi paksus, m	Kasuliku kihi jääkpaksus, m	Lamami, sügavus, m	Lamami abs kõrgus, m	Veetase, m		
	X	Y	Z						süg maap, m	abs	mõõtmise aeg
PA-1	6577283,339	702901,645	58,13	21,70	1,00	20,70	21.7+	36,43	13,50	44,63	25.07.2017
PA-2	6577220,567	703074,081	55,86	21,75	0,85	20,90	21.75+	34,11	12,50	43,36	25.07.2017
NP-3/PA-3	6577351,241	702922,378	49,68	18,55	0,00	18,55	18,55	31,13	6,15	43,53	26.07.2017
PA-4	6577252,569	702991,177	57,12	21,70	1,00	20,70	21.7+	35,42	12,50	44,62	26.07.2017
PA-5	6577387,952	703082,772	43,95	13,90	0,00	13,90	13.9+	30,05	0,25	43,70	26.07.2017
PA-6	6577328,533	703011,296	43,62	12,75	0,00	12,75	12.75+	30,87	0,10	43,52	26.07.2017
PA-7	6577285,406	703082,822	44,12	13,00	0,00	13,00	13.0+	31,12	0,50	43,62	26.07.2017
PA-8	6577403,046	703016,385	44,18	13,75	0,00	13,75	13.75+	30,43	0,50	43,68	27.07.2017
PA-9	6577409,378	702933,752	50,12	18,75	0,00	18,75	18.75+	31,37	6,00	44,12	27.07.2017
NP-1	6577320,797	703068,681	46,22	2,75	0,00	2,75	-	-	-	-	-
NPŠ-2	6577288,507	703048,269	47,51	8,30	0,00	8,30	-	-	-	-	-
Š-3	6577388,405	702979,706	43,48	1,50	0,00	1,50	-	-	0,00	43,48	27.07.2017
Š-4	6577340,204	702975,890	43,63	2,00	0,00	2,00	-	-	0,10	43,53	27.07.2017

2021. a kaevandid

Kaevandi nr	Koordinaadid			Kaevandi süg., m	Katendi paksus, m	Veetase, m	
	X	Y	Z			süg. maap., m	mõõtmise aeg
Š-1	6576661,73	702783,65	48,40	3,0	3,0	3,0	06.07.2021
Š-2	6576901,65	702715,45	49,78	4,1	3,1	-	-
Š-3	6577101,66	702688,98	49,21	3,5	1,2	-	-
Š-4	6577091,97	702801,41	50,30	2,6	1,0	-	-
Š-7	6577014,96	702909,01	46,47	3,2	2,2	-	-
Š-8	6576846,24	702920,06	48,71	1,7	0,5	-	-
Š-9	6576783,94	702861,84	48,88	2,5	0,1	-	-
Š-10	6576772,26	702811,41	49,65	2,5	1,3	-	-
Š-11	6576663,19	702889,33	49,43	3,6	2,9	-	-
Š-12	6576642,34	702951,44	49,06	3,0	1,3	-	-
Š-13	6576524,36	702968,42	48,21	2,0	0,3	-	-
Š-14	6576359,27	702945,43	48,79	2,5	1,4	-	-
Š-16	6576227,53	702904,84	49,26	3,5	2,4	-	-
Š-17	6576076,83	702880,76	47,97	3,0	0,5	-	-
Š-18	6575968,00	702915,11	45,58	3,0	2,4	-	-
Š-19	6575904,39	702909,80	44,93	2,5	0,2	-	-
Š-20	6575833,70	702896,38	46,85	2,5	0,1	-	-
Š-21	6576002,14	702835,07	50,56	3,5	2,5	-	-
Š-22	6576097,29	702841,25	49,20	2,0	0,0	-	-
Š-23	6576265,48	702860,62	49,86	2,5	0,2	-	-
Š-24	6576400,71	702885,56	49,89	2,5	0,2	-	-
Š-25	6576528,30	702872,78	50,15	3,0	1,3	-	-
Š-26	6576882,86	702873,57	49,33	0,7	0,5	-	-
Š-27	6576846,63	702836,59	49,46	0,5	0,5	-	-
Š-28	6576795,25	702811,41	49,68	1,4	1,2	-	-
Š-29	6576711,54	702877,42	50,16	2,5	1,6	-	-
Š-30	6576584,08	702883,29	49,87	1,2	1,2	-	-
Š-31	6576499,51	702902,95	49,75	1,6	1,6	-	-
Š-32	6576134,62	702918,95	45,95	1,5	1,4	-	-
Š-33	6575941,66	702910,57	45,09	2,6	2,5	3,0	29.07.2021

2021. a sondeerimispunktid

Kaevandi nr	Koordinaadid			Kaevandi süg., m
	X	Y	Z	
T-2	6575523,22	702758,38	47,60	3,30
T-5	6575777,35	702757,69	47,19	1,60
T-7	6575923,13	702772,21	47,13	2,20
T-9	6576246,79	702728,71	46,73	4,85
T-13	6576426,67	702746,09	46,65	2,60